WORTHINGTON, SKILLING, HELLE & JACKSON  Civil & Structural Engineers

PROJECT THE WORLD TRADE CENTER | TITLE COLUMN SCHEDULE | DATE 5-15-67

| REVISIONS |
|---|
| 5-1-68 |
| 6-28-68 |
| 4-4-69 |

| | J4-14 | | J4-16 | J4-17 | | J4-19 | J4-20 |
|---|---|---|---|---|---|---|---|
| El. 332' | | | | | | | Btm. of 12 Girder |
| El. 310' | Part of Truss JT-5 | | Part of Truss JT-5 | | | | |
| El. 290' | | | 14 WF 264 (Fy=50) | | | | 14 WF 550 (Fy=50) |
| El. 274' | Part of Truss JT-4 14 WF 287 (Fy=50) | | Det. 7 10-JK2-36 14 WF 550 (Fy=50) | | | | |
| El. 264' | | | 14 WF 605 +PL 14×3 (B.S.) (Fy=46) | | | 14 WF 87 (Fy=42) | 14 WF 550 (Fy=50) |
| Top of base PL | Splice, see Det. 5 10-JK2-36 18×17 I 2 PLS 17×4 1 PL 10×2½ (Fy=50) El. 283'-4" | | 14 WF 605 ▲ +PL 14×3 (B.S.) (Fy=46) El. 283'-4" | 14 WF 211 (Fy=50) El. 283'-4" | | | |
| Base Plate | 67×8×6'-1" | | 69×8¾×6'-9" | 40×4×3'-7" | | | |

✱ Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4..
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

LICENSED PROFESSIONAL ENGINEER LESLIE E. ROBERTSON No. 34360 UNIVERSITY OF THE STATE OF NEW YORK

DRAWN S.C.
REVIEWED E.L.

10-J1-19

B