WORTHINGTON, SKILLING, HELLE & JACKSON Civil & Structural Engineers

PROJECT THE WORLD TRADE CENTER | TITLE COLUMN SCHEDULE | DATE 5-15-67

REVISIONS
5-1-68
6-7-68

	J4-21	J4-22
El. 332'		
El. 313'		
El. 290'		
El. 274'		14 WF 211 (Fy-50)
El. 264'		
Top of base Pl	Bott of Pl Girder El. 283'-4" — 14 WF 550 (Fy=50)	El. 283'-4" — 14 WF 398 (Fy=50)
Base Plate	67 × 8 × 6'-1"	55 × 6½ × 4'-11"

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4..
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-J1-20

LICENSED PROFESSIONAL ENGINEER LESLIE E. ROBERTSON No. 34360 UNIVERSITY OF THE STATE OF NEW YORK

B