WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
2-9-68
4-5-68
6-17-68

	J5-1		J5-3	J5-4	J5-5	J5-6	J5-7
El. 332'				10-JK2-17	10-JK2-17	10-JK2-17	10-JK2-17
El. 310'	*						
El. 294'	14WF158 (Fy=50)		14WF87 (Fy=50)	14WF314 (Fy=50)	14WF264 (Fy=50)	14WF287 (Fy=50)	14WF314 (Fy=50)
El. 284'				Truss JT-1 See dwg. 11-J1-2			
El. 274'							
El. 264'	14WF314 (Fy=50)		14WF167 (Fy=50)		14WF370 (Fy=50)	14WF370 (Fy=50)	14WF426 (Fy=50)
El. 253	▲ 14WF314 (Fy=50)		▲ 14WF167 (Fy=50)	14WF237 (Fy=50)	▲ 14WF370 (Fy=50)	▲ 14WF370 (Fy=50)	▲ 14WF426 (Fy=50)
Top of base Pl	El. 244'-6"		El. 244'-6"	El. 241'	El. 241'	El. 241'	El. 241'
Base Plate	45 × 4⅝ × 4'-0"		31 × 2¾ × 2'-9"	49 × 5⅝ × 4'-3"	60 × 7¼ × 5'-3"	60 × 7¼ × 5'-3"	63 × 7¾ × 5'-7"

✱ Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-J1-22

LESLIE E. ROBERTSON — REGISTERED PROFESSIONAL ENGINEER — No. 34360 — STATE OF NEW YORK — UNIVERSITY OF THE STATE OF NEW YORK

A