WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
5-1-68
6-7-68
6-17-68

	J5-15		J5-17	J5-18	J5-19	J5-20	J5-21
El. 332'					10-JK2-77		
El. 310'							
El. 290'					14 WF 500 (Fy=50)		14 WF 237 (Fy=50)
El. 274'	14 WF 158 (Fy=50)		14 WF 142 (Fy=50)		℄ Girder		
El. 264'	14 WF 158 (Fy=50)		14 WF 142 (Fy=50)	Bott. of ℄ Girder See dwg. 14 WF 370 (Fy=50)	14 WF 61 (Fy=42)	Bott. of ℄ Girder See dwg. 14 WF 550 (Fy=50)	14 WF 455 (Fy=50)
Top of base ℄	See detail 10-JK4-4B 14 WF 158 (Fy=50) El. 243'-4"		14 WF 142 (Fy=50) ▲ El. 243'-4"	See dwg. 14 WF 370 (Fy=50) ▲ El. 241'-9"	See detail on 10-JK2-35	14 WF 550 (Fy=50) ▲ El. 241'	14 WF 455 (Fy=50) ▲ El. 241'
Base Plate	35 × 3½ × 3'-1"		33 × 3⅛ × 3'-0"	53 × 6¼ × 4'-9"		59 × 7 × 5'-5"	55 × 6½ × 5'-0"

LICENSED PROFESSIONAL ENGINEER LESLIE E. ROBERTSON No. 34260 UNIVERSITY OF THE STATE OF NEW YORK

✱ Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4..
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-J1-24