WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
2-9-68
6-17-68

	J7-1	J7-2	J7-3	J7-4	J7-5	J7-6	J7-7
El. 332'		Det. 10/4 10-JK2-7	10-JK2-17	10-JK2-17	10-JK2-17	10-JK2-17	10-JK2-17
El. 310'	*						
El. 294'							
El. 284'	14 WF 150 (Fy=50)	14 WF 370 (Fy=50)	14 WF 342 (Fy=50)	14 WF 314 (Fy=50)	14 WF 287 (Fy=50)	14 WF 287 (Fy=50)	14 WF 287 (Fy=50)
El. 274'							
El. 264'	14 WF 246 (Fy=50)	14 WF 455 (Fy=50)	14 WF 455 (Fy=50)	14 WF 426 (Fy=50)	14 WF 370 (Fy=50)	14 WF 370 (Fy=50)	14 WF 370 (Fy=50)
El. 253	▲ 14 WF 246 (Fy=50)	▲ 14 WF 455 (Fy=50)	▲ 14 WF 455 (Fy=50)	▲ 14 WF 426 (Fy=50)	▲ 14 WF 370 (Fy=50)	▲ 14 WF 370 (Fy=50)	▲ 14 WF 370 (Fy=50)
Top of base Pl at El. 241'							
Base Plate	45 × 5⅛ × 3'-11"	64 × 8 × 5'-9"	64 × 8 × 5'-9"	63 × 7¾ × 5'-7"	60 × 7¼ × 5'-3"	60 × 7¼ × 5'-3"	60 × 7¼ × 5'-3"

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

10-J1-32