WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
10-20-67
11-8-67
6-17-68
1-8-69

	J9-1	J9-2	J9-3	J9-4	J9-5	J9-6	J9-7
El. 332'	10-JK2-17	10-JK2-17	10-JK2-17	10-JK2-17	10-JK2-17	10-JK2-38A	
El. 310'							*
El. 294'	14 WF 398 (Fy=50)	14 WF 370 (Fy=50)	14 WF 370 (Fy=50)	14 WF 370 (Fy=50)	14 WF 370 (Fy=50)	14 WF 398 (Fy=50)	14 WF 136 (Fy=50)
El. 284'							
El. 274'							
El. 264'	14 WF 426 (Fy=50)	14 WF 426 (Fy=50)	14 WF 426 (Fy=50)	14 WF 426 (Fy=50)	14 WF 426 (Fy=50)	14 WF 426 (Fy=50)	14 WF 167 (Fy=50)
El. 253	▲ 14 WF 500 (Fy=50)	▲ 14 WF 455 (Fy=50)	▲ 14 WF 455 (Fy=50)	▲ 14 WF 455 (Fy=50)	▲ 14 WF 455 (Fy=50)	▲ 14 WF 500 (Fy=50)	▲ 14 WF 228 (Fy=50)
Top of base Pl at El. 241'							
Base Plate	60 × 7½ × 5'-5"	60 × 7½ × 5'-5"	60 × 7½ × 5'-5"	60 × 7½ × 5'-5"	60 × 7½ × 5'-5"	62 × 7½ × 5'-6"	44 × 4⅞ × 3'-10"

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

DRAWN S.C.
REVIEWED E.L.

*Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲See detail on 10-JK4-3 and 4.
■Splice 3" above slab. See note on 10-JK2-2.
●See detail on 10-JK2-30.

10-J1-43