WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
10-20-67
11-8-67

J10-51

El. 332'

El. 310'

J1-661 level

El. 294'

14WF87 (105-A1)

El. 284'

El. 274'

14WF95 (1) (Fy=50)

El. 264'

14WF127 (▲) (Fy=50)

El. 253

Top of base Pl at El. 241'

Base Plate 32 x 3 - 2'-9"

*▲ Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown. See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-11-67

LICENSED PROFESSIONAL ENGINEER LESLIE E. ROBERTSON No. 34360 UNIVERSITY OF THE STATE OF NEW YORK

A