WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
5-1-68

| | J12-8 |
|---|---|
| El. 332' | |
| El. 310' | * |
| El. 290' | 14 WF 287 (Fy=50) |
| El. 279'-3" | |
| El. 264' | 14 WF 550 (Fy=50) |
| El. 253 | ▲ 14 WF 550 (Fy=50) |
| Top of Base Pl. El. 243'-4" | |
| Base Plate | 53 × 6¼ × 5'-0" |

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-J1-52

LICENSED PROFESSIONAL ENGINEER LESLIE E. ROBERTSON No. 34350 UNIVERSITY OF THE STATE OF NEW YORK

C