WORTHINGTON, SKILLING, HELLE & JACKSON  Civil & Structural Engineers

PROJECT THE WORLD TRADE CENTER | TITLE COLUMN SCHEDULE | DATE 5-15-67

REVISIONS
10-20-67
11-8-67

| | J14-1 | J14-2 | J14-3 | J14-4 | J14-5 | J14-6 |
|---|---|---|---|---|---|---|
| El. 332' | | | | | | |
| El. 310' | | | | | | |
| Street level | | | | | | |
| El. 294' | 14 WF 103 (Fy=50) | | 14 WF 150 (Fy=50) | 14 WF 142 (Fy=50) | 14 WF 211 (Fy=50) | |
| El. 284' | | | | | | 14 WF 61 (Fy=50) |
| El. 274' | 14 WF 103 (Fy=50) + | 14 WF 74 (Fy=50) | 14 WF 176 (Fy=50) + | 14 WF 167 (Fy=50) + | 14 WF 228 (Fy=50) + | 14 WF 74 (Fy=50) + |
| El. 264' | ▲ | ▲ | ▲ | ▲ | ▲ | ▲ |
| El. 253 | 14 WF 119 (Fy=50) | 14 WF 111 (Fy=50) | 14 WF 264 (Fy=50) | 14 WF 246 (Fy=50) | 14 WF 320 (Fy=50) | 14 WF 111 (Fy=50) |
| Top of base Pl at El. 241' | | | | | | |
| Base Plate | 32 × 3 × 2'-7" | 32 × 3 × 2'-9" | 48 × 5¼ × 4'-4" | 48 × 5¼ × 4'-2" | 50 × 5 × 4'-0" | 32 × 3 × 2'-9" |

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-J1-56

LICENSED PROFESSIONAL ENGINEER LESLIE E. ROBERTSON No. 34360 UNIVERSITY OF THE STATE OF NEW YORK