WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
10-20-67
11-8-67

	J15-1	J15-2	J15-3	J15-4	J15-5
El. 332'					
El. 310'					
Street level					
El. 294'	14 WF 68 (Fy=50)	14 WF 111 (Fy=50)	14 WF 136 (Fy=50)	⊙ 14 WF 167 (Fy=50)	14 WF 87 (Fy=50)
El. 284'					
El. 274'					
El. 264'	14 WF 84 (Fy=50)	14 WF 142 (Fy=50)	14 WF 167 (Fy=50)	14 WF 202 (Fy=50)	14 WF 111 (Fy=50)
El. 253	▲ 14 WF 127 (Fy=50)	▲ 14 WF 219 (Fy=50)	▲ 14 WF 237 (Fy=50)	▲ 14 WF 314 (Fy=50)	▲ 14 WF 158 (Fy=50)
Top of base Pl at El. 241'					
Base Plate	34 × 3 3/8 × 3'-1"	46 × 4 3/4 × 4'-2"	46 × 4 7/8 × 4'-1"	54 × 5 1/2 × 4'-3"	38 = 3 3/4 = 3'-4"

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
⊙ See detail on 10-JK2-30.

10-J1-60

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

A