WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
10-20-67
11-8-67

	J17-1	J17-2	J17-3	J17-4	J17-5
El. 332'					
El. 310'					
Street level					
El. 294'	14 WF 68 (Fy=50)	14 WF 111 (Fy=50)	14 WF 111 (Fy=50)	14 WF 167 (Fy=50)	14 WF 87 (Fy=50)
El. 284'					
El. 274'	14 WF 78 (Fy=50)	14 WF 136 (Fy=50)	14 WF 142 (Fy=50)	14 WF 202 (Fy=50)	14 WF 111 (Fy=50)
El. 264'					
El. 253	14 WF 119 (Fy=50)	14 WF 202 (Fy=50)	14 WF 211 (Fy=50)	14 WF 314 (Fy=50)	14 WF 158 (Fy=50)
Top of base Pl at El. 241'					
Base Plate	28 × 2 5/8 × 2'-4"	42 × 4 1/4 × 3'-6"	42 × 4 1/4 × 3'-10"	54 × 5 1/2 × 4'-3"	38 × 3 3/4 × 3'-4"

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-11-64