WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
10-20-67
11-8-67

	J23-51
El. 332'	
El. 310'	
El. 294'	
El. 284'	14 WF 43
El. 274'	14 WF 43 (Fy=50) ●
El. 264'	14 WF 78 (Fy=50) ▲
El. 253	
Top of base Pl at El. 241'	
Base plate	30×2½×2'-1"

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 1" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-JJ-76

LESLIE E. ROBERTSON — REGISTERED PROFESSIONAL ENGINEER — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK