WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS: 5-1-68

| | J71-1 | J71-2 | J71-3 | J71-4 | J71-5 | J71-6 | J71-7 |
|---|---|---|---|---|---|---|---|
| El. 332' | | | | | | | |
| El. 310' | | | | | | | |
| El. 290' | | 14WF111 (Fy=50) | 14WF127 (Fy=50) | 14WF127 (Fy=50) | 14WF136 (Fy=50) | 14WF176 (Fy=50) | 14WF167 (Fy=50) |
| El. 279'-3" | | | | | | | |
| El. 264' | | 14WF314 (Fy=50) | 14WF342 (Fy=50) | 14WF314 (Fy=50) | 14WF342 (Fy=50) | 14WF426 (Fy=50) | 14WF398 (Fy=50) |
| El. 253 | 14WF61 (Fy=42) | ▲ 14WF314 (Fy=50) | ▲ 14WF342 (Fy=50) | ▲ 14WF314 (Fy=50) | ▲ 14WF342 (Fy=50) | ▲ 14WF426 (Fy=50) | ▲ 14WF398 (Fy=50) |
| Top of Base Pl. | El. 241' | El. 241' | El. 241' | El. 241' | El. 241' | El. 241' | El. 241' |
| Base Plate | 20×1¾×2'-0" | 40×4×3'-7" | 44×4⅞×3'-10" | 42×4⅝×3'-9" | 44×5×3'-11" | 50×5⅝×4'-5" | 48×5⅝×4'-4" |

✱ Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-J1-81

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK