WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
5-1-68
6-7-68
10-15-68

	J73-8	J73-9	J73-10	J73-11	J73-12		
El. 332'							
El. 310'							
El. 290'							
El. 279'-3"	14WF87 (Fy=50)	14WF111 (Fy=50)		14WF111 (Fy=50)	14WF87 (Fy=50)		
El. 264'	Temp. bracing 20×12.7 2 PL's 12×½ 1 PL 17×¾ (Fy=50)	Temp. bracing 20×12.7 2 PL's 12×½ 1 PL 17×¾ (Fy=50)		Temp. bracing 20×12.7 2 PL's 12×½ 1 PL 17×¾ (Fy=50)	Temp. bracing 20×12.7 2 PL's 12×½ 1 PL 17×¾ (Fy=50)		
El. 253	Scc 10-JK2-358 14 WF 176 (Fy=50)	Scc 10-JK2-355 14 WF 193 (Fy=50)	▲ 14 WF 87 (Fy=50)	Scc 10-JK2-356 14 WF 193 (Fy=50)	Scc 10-JK2-356 14 WF 176 (Fy=50)		
Top of Base Pl.	El. 243'-4"	El. 243'-4"	El. 243'-4"	El. 243'-4"	El. 243'-4"		
Base Plate	37×3¾×3'-4"	38×3⅞×3'-5"	20×2⅛×2'-4"	38×3⅞×3'-5"	37×3¾×3'-4"		

LICENSED PROFESSIONAL ENGINEER LESLIE E. ROBERTSON REG. 54980 STATE OF NEW YORK

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-J1-88

C