WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT THE WORLD TRADE CENTER | TITLE COLUMN SCHEDULE | DATE 5-15-67

REVISIONS
5-1-68
6-7-68

	J74-7	J74-8	J74-9	J74-10	J74-11		
El. 332'							
El. 310'							
El. 290'	Det. 5 10-JK2-41 14 WF 264 (Fy=50)	Det. 1 10-JK2-41 14 WF 211 (Fy=50)	Det. 3 10-JK2-41 14 WF 167 (Fy=50)	Det. 3 10-JK2-41 14 WF 167 (Fy=50)	Det. 1 10-JK2-41 14 WF 211 (Fy=50)		
El. 279'3"	Temp. bracing 20×12 I 2 PL 12×3 1 PL 14×2 (Fy=50)	Temp. bracing 20×12 I 2 PL 12×2¾ 1 PL 14½×1½ (Fy=50)	Temp. bracing 20×12 I 2 PL 12×2½ 1 PL 15×1 (Fy=50)	Temp. bracing 20×12 I 2 PL 12×2½ 1 PL 15×1 (Fy=50)	Temp. bracing 20×12 I 2 PL 12×2¾ 1 PL 14½×1½ (Fy=50)		
El. 264'							
El. 253	Sec 10-JK2-356 14 WF 398 (Fy=50)	Sec 10-JK2-356 14 WF 342 (Fy=50)	Sec 10-JK2-356 14 WF 287 (Fy=50)	Sec 10-JK2-358 14 WF 314 (Fy=50)	Sec 10-JK2-358 14 WF 342 (Fy=50)		
Top of Base Pl.	El. 243'-4"	El. 243'-4"	El. 243'-4"	El. 243'-4"	El. 243'-4"		
Base Plate	56×6½×5'-0"	53×6¼×4'-9"	49×5⅝×4'-3"	48×5⅝×4'-4"	53×6⅛×4'-9"		

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

LICENSED PROFESSIONAL ENGINEER LESLIE E. ROBERTSON No. 34460 UNIVERSITY OF THE STATE OF NEW YORK

10-J1-91