WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
5-1-68
6-7-68
6-28-68

	J75-1	J75-2	J75-3	J-75-4	J75-5	J75-6
El. 332'						
El. 310'						
El. 290'			14WF228 (Fy=50)	14WF228 (Fy=50)	14WF211 (Fy=50)	14WF150 (Fy=50)
El. 279'3		14WF136 (Fy=50)	Temp bracing	Det.6 10-JK2-41 Temp bracing	Det.7 10-JK2-41 Temp bracing	Det.8 10-JK2-41 Temp bracing
El. 274'	Temp bracing	Temp. bracing	14WF342 (Fy=50)			20x12 I 2 PL 12x2 1 PL 16x1 (Fy=50)
El. 264'	Bottr. of 12 Girder 14WF398 (Fy=50)	12 Girder 14WF398 (Fy=50)				See detail on 10-JK2-35B
El. 253	17x17 I 2 PL 17x4 1 PL 9x2½ (Fy=50)	17x17 I 2 PL 17x4 1 PL 9x2½ (Fy=50)	14WF426 (Fy=50)	20x12 I 2 PL 12x5 1 PL 10x3 (Fy=50)	20x12 I 2 PL 12x5 1 PL 10x3 (Fy=50)	14WF287 (Fy=50)
Top of Base Pl.	El. 243'-4"	El. 243'-4"	El. 243'-4"	El. 243'-4"	El. 243'-4"	El. 243'-4"
Base Plate	69x8½x6'-4"	69x9x6'-4"	59x7¼x5'-5"	55x7x4'-11"	53x7x4'-9"	47x5⅜x4'-2"

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-J1-92

LICENSED LESLIE E. ROBERTSON NO. 34250 UNIVERSITY OF THE STATE OF NEW YORK