WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
1-13-69

	K30-1	K30-2	K30-3	K30-4	K30-5	K30-6	K30-7
El. 332'							
El. 310'	14 WF 84 (Fy=50)	14 WF 228 (Fy=50)	14 WF 84 (Fy=50)	14 WF 84 (Fy=50)	14 WF 228 (Fy=50)	14 WF 84 (Fy=50)	14 WF 228 (Fy=50)
El. 290'							
El. 279'-3"							
El. 264'							
El. 253							
Top of Base Pl.							
Base Plate							



✱ Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

DRAWN S.C.
REVIEWED R.T. & E.L.

10-K1-206

C