WORTHINGTON, SKILLING, HELLE & JACKSON Civil & Structural Engineers

PROJECT THE WORLD TRADE CENTER | TITLE COLUMN SCHEDULE | DATE 5-15-67

REVISIONS
10-20-67
11-8-67
12-23-71
1-15-72
11-27-72

	K31-1	K31-2	K31-3	K31-4	K31-5	K31-6	K31-7
El. 332'			See Dwg. Book 13		See D.B. 13	See D.B. 13	12-JK2-181
El. 310'							14 WF 370 (Fy=50)
Street level	14 WF 111 (Fy=50)	14 WF 184 (Fy=50)	14 WF 264 (Fy=50)		14 WF 426 (Fy=50)	See 19-1053 for new cover pl. 14 WF 398 (Fy=50)	14 WF 398 (Fy=50)
El. 294'							
El. 284'							
El. 274'	14 WF 127 (Fy=50)	14 WF 246 (Fy=50)	14 WF 320 (Fy=50)		14 WF 320 + ℄ 23×3 (B.S.) (Fy=42)	14 WF 320 + ℄ 23×2⅞ (B.S.) (Fy=42)	14 WF 320 + ℄ 23×2⅞ (B.S.) (Fy=42)
El. 264'							
El. 253	14 WF 202 (Fy=50)	14 WF 370 (Fy=50)	14 WF 455 (Fy=50)	14 WF 84 (Fy=50)			
Top of base ℄ at El. 241'							
Base Plate	40×3¾×5'-1"	54×5⅞×4'-3"	62×7×4'-9"	20×2⅛×2'-4"	60×7×5'-6"	60×7×5'-5"	60×7×5'-6"

LICENSED PROFESSIONAL ENGINEER LESLIE E. ROBERTSON No. 34360 UNIVERSITY OF THE STATE OF NEW YORK

DRAWN S.C.
REVIEWED E.L.

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-K1-207