WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
10-20-67
11-8-67
6-7-68
11-5-68
12-3-68
10-14-69

	K31-8	K31-9	K31-10	K31-11	K31-12	K31-5A
El. 332'						
El. 310'	14 WF 136 (Fy=50)	14 WF 150 (Fy=50)	14 WF 95 (Fy=50)			
El. 294'	14 WF 176 (Fy=50)	14 WF 176 (Fy=50)	14 WF 184 (Fy=50)	14 WF 150 (Fy=50)		
El. 284'					14 WF 61 (Fy=42)	
El. 279'-3"						
El. 274'						
El. 264'	14 WF 550 (Fy=50)	14 WF 550 (Fy=50)	14 WF 550 (Fy=50)	14 WF 500 (Fy=50)		
El. 257'-0"					14 WF 111 (Fy=50)	
El. 253						14 WF 68 (Fy=50)
Top of base Pl at El. 241'						
Base Plate	54 × 5½ × 4'-3"	54 × 5½ × 4'-3"	46 × 4¾ × 4'-2"	38 × 3¾ × 3'-4"	30 × 3 × 2'-0"	25 × 2½ × 2'-6"

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-10

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

DRAWN S.C.
REVIEWED E.L.

10-K1-208