WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
2-4-69
2-11-69
4-4-69
5-29-69
1-15-72
11-27-72

	K37-1.	K37-2	K37-3	K37-4	K37-5	K37-6	K37-7
El. 332'							12-JK2-181
El. 310'		*See Dwg. Book 13.		See D.B. 13	See D.B. 13	*See D.B. 13	* 14 WF 398 (Fy=50)
El. 294'	Street level 14 WF 150 (Fy=50)	14 WF 246 (Fy=50)		El. 304'-0" 14 WF 455 (Fy=50)	El. 306'-0" * 14 WF 665 (Fy=46)	14 WF 730 (Fy=46)	14 WF 665 (Fy=46)
El. 284'							
El. 274'	14 WF 237 (Fy=50)	14 WF 455 (Fy=50)		14 WF 500 (Fy=50)	14 WF 730 (Fy=46)	14 WF 730 (Fy=46)	14 WF 665 (Fy=46)
El. 264'							
El. 253'	▲ 14 WF 500 (Fy=50)	▲ 14 WF 605 (Fy=46)	El. 261'-6" 14 WF 264 (Fy=50)		El. 257' 14 WF 730 (Fy=46)	El. 257 14 WF 730 (Fy=46)	
Top of base Pl at El. 241'							
Base Plate	47 = 5⅛ x 3'-11"	47 = 5⅛ x 3'-11"	28 x 2⅜ x 2'-4"	61 x 7¼ x 5'-1"	74 x 9 x 6'-2"	74 x 9 x 6'-2"	67 x 8 x 5'-7"

✱ Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34350 — STATE OF NEW YORK

DRAWN: S.C.
REVIEWED: E.L.

10-K1-215