WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
1-13-69

	K39-1	K39-2	K39-3	K39-4	K39-5	K39-6	K39-7
El. 332'							
El. 310'	14 WF 202 (Fy=50)	14 WF 264 (Fy=50)	14 WF 202 (Fy=50)	14 WF 202 (Fy=50)	14 WF 264 (Fy=50)	14 WF 202 (Fy=50)	14 WF 264 (Fy=50)
El. 290'							
El. 279'3"							
El. 264'							
El. 253							
Top of Base Pl.							
Base Plate							

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — REGISTERED IN THE STATE OF NEW YORK

DRAWN S.C.
REVIEWED R.T. & E.L.

10-K1-219