WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
2-4-69
2-11-69
1-15-72
11-27-72

	K41-1	K41-2	K41-3	K41-4	K41-5	K41-6	K41-7
El. 332'							12-JK2-181
El. 310'			* See Dwg Book 13	* See D.B. 13	* See D.B. 13	* See D.B. 13	* 14 WF 398 (Fy=50)
Street level	14 WF 95 (Fy=50)	14 WF 158 (Fy=50)	14 WF 246 (Fy=50)	14 WF 500 (Fy=50)	14 WF 665 (Fy=46)	14 WF 320 + PL 22 × 2¾ (B.S.) (Fy=42)	14 WF 605 (Fy=46)
El. 284'							
El. 274'	14 WF 142 (Fy=50)	14 WF 237 (Fy=50)	14 WF 455 (Fy=50)	14 WF 550 (Fy=50)	14 WF 320 + PL 24 × 3 (B.S.) (Fy=42)	14 WF 320 + PL 22 × 2¾ (B.S.) (Fy=42)	14 WF 320 + PL 22 × 2¾ (B.S.) (Fy=42)
El. 264'							
El. 253'	▲ 14 WF 287 (Fy=50)	▲ 14 WF 500 (Fy=50)	14 WF 605 (Fy=46)				
Top of base Pl at El. 241'							
Base Plate	33 × 3⅛ × 2'-9"	47 × 5⅛ × 3'-11"	48 × 5¼ × 4'-0"	61 × 7¼ × 5'-1"	74 × 9 × 6'-2"	74 × 9 × 6'-2"	67 × 8 × 5'-7"

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

DRAWN S.C.

REVIEWED E.L.

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-K1-221

A