WORTHINGTON, SKILLING, HELLE & JACKSON Civil & Structural Engineers

PROJECT THE WORLD TRADE CENTER | TITLE COLUMN SCHEDULE | DATE 5-15-67

REVISIONS
12-3-68
10-23-69
11-27-72

	K45-8
El. 332'	3'-0" — See Dwg. Book 13
El. 310'	
El. 294'	14WF237 (Fy=50)
El. 284'	
El. 274'	14WF287 (Fy=50)
El. 264' ▲	
El. 253	14WF287 (Fy=50)
Top of base Pl	
	El. 241'-0"
Base Plate	46 x 5 x 3'-10"

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

DRAWN S.C.
REVIEWED E.L.

10-K1-231

A