WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
- 1-17-69
- 3-1-69
- 3-12-69
- 3-21-69
- 6-13-69
- 11-27-72

	K49-51	K49-52	K49-53	K49-54	K49-55	K49-56
El. 332'						
El. 310'				* See Dwg. Book 13	El. 310'-4 See DB. 13	
El. 294'	Street level 14WF84 (Fy=50)			14WF320 +12 22x2 (B.S.) (Fy=42)	14WF320 +12 22x2 (B.S.) Fy=42	
El. 284'		14WF53 (Fy=50)				
El. 274'				14WF320 +12 22x2½ (B.S.) (Fy=42)	14WF320 +12 22x2½ (B.S.) (Fy=42)	(See 12-JK1-47) 14WF500 (Fy=36)
El. 264'	14WF184 (Fy=36)	(See 12-JK1-47) 14WF111 (Fy=36)	2 girder			
El. 253			14WF142 (Fy=36)	14WF320 +12 22x2¾ (B.S.) (Fy=42) ▲	14WF320 +12 22x2¾ (B.S.) (Fy=42) ▲	
Top of base Pl.	El. 248'-0"	El. 248'-0"	El. 241'-0"	El. 241'-0"	El. 241'-0"	
Base Plate	31x23½x2'-7"	28x23⅜x2'-4"	30x25⅛x2'-4"	79x10x7'-2"	79x10x7'-2"	

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — STATE OF NEW YORK

DRAWN S.C.
REVIEWED E.L.

10-K1-239

A