WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
3-1-69
3-12-69
3-21-69
10-23-69
11-27-72

	K51-1	K51-2	K51-3	K51-4	K51-5	K51-6	K51-7
El. 332'		* See Dwg. Book 13	* See D.B. 13	* See D.B. 13	* See D.B. 13	14 WF 142 (Fy=50)	P.C. Girder 14 WF 87 (Fy=50)
El. 310'							
STREET LEVEL							
El. 294'	14WF487 (Fy=50)	14WF455 (Fy=50)	14WF320 + PL 23×2¾ (B.S.) (Fy=42)	14WF320 + PL 23×2⅞ (B.S.) (Fy=42)	14WF398 (Fy=50)	14WF219 (Fy=50)	14WF246 (Fy=50)
El. 284'							
El. 274'	14WF119 (Fy=50)	14WF500 (Fy=50)		14WF320 + PL 24×1¾ (B.S.) (Fy=42)	14WF455 (Fy=50)	14WF264 (Fy=50)	14WF287 (Fy=50)
El. 270'-4"							
El. 264'	P.C. girder	▲	▲	▲	▲	▲	
El. 253		14WF550 (Fy=50)	14WF320 + PL 23×3 (B.S.) (Fy=42)	14WF320 + PL 24×3⅜ (B.S.) (Fy=42)	14WF500 (Fy=50)	14WF320 (Fy=50)	14WF342 (Fy=50)
Top of base Pl		El. 241'-0"	El. 241'-0"	El. 241'-0"	El. 241'-0"	El. 241'-0"	El. 235'-6½"
Base Plate		73×9×6'-1"	85×17⅜×7'-1"	88×11×7'-4"	69×8½×5'-9"	57×6½×4'-8"	56×6½×4'-8"

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

DRAWN J.A.
REVISED E.L.

10-K1-241

A