WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
1-6-69
1-17-69
3-1-69
3-12-69
3-21-69
11-27-72.

	K55-1	K55-2	K55-3	K55-4	K55-5	K55-6	K55-7
El. 332'							
		*See Dwg. Book 13	*See D.B. 13	*See D.B. 13	*See D.B. 13	*See D.B. 13	
El. 310'							
Splice level							
El. 294'	14WF167 (Fy=50)	14WF455 (Fy=50)	14WF320 +2 22½x3 (B.S.) (Fy=42)	14WF320 +2 22x2⅜ (Fy=42)	14WF320 +2 22x2⅜ (Fy=42)	14WF320 +2 22x2 (B.S.) (Fy=42)	
El. 284'							
El. 274'	14WF202 (Fy=50)	14WF500 (Fy=50)	14WF320 +2 22x3½ (B.S.) (Fy=42)	14WF320 +2 22x2⅝ (Fy=42)	14WF320 +2 22x2⅝ (Fy=42)	14WF320 +2 22x2¼ (B.S.) (Fy=42)	
El. 264'							
El. 253	14WF237 (Fy=50)	14WF550 (Fy=50)	▲14WF320 +2 24x3½ (B.S.) (Fy=42)	▲14WF320 +2 23x3 (B.S.) (Fy=42)	▲14WF320 +2 23x3 (B.S.) (Fy=42)	▲14WF320 +2 22x2¾ (B.S.) (Fy=42)	
Top of base ℄	El. 248'-0"	El. 241'-0"	El. 241'-0"	El. 241'-0"	El. 241'-0"	El. 241'-0"	
Base Plate	47 x 5⅛ x 3'-11"	73 x 9 x 6'-1"	88 x 11 x 7'-4"	83 x 10¼ x 6'-11"	83 x 10⅛ x 6'-11"	79 x 9¾ x 6'-7"	

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

DRAWN S.C.
REVIEWED E.L.

10-K1-249