WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
10-15-68
1-6-69
3-1-69
3-12-69
3-21-69
11-27-72

	K57-1	K57-2	K57-3	K57-4	K57-5	K57-6	K57-7
El. 332'							
El. 310'		14WF500 (Fy=50) ▲ See Dwg. Book 13		See D.B. 13	See D.B. 13	See D.B. 13	
El. 294'	1'-0" ℄ Girder 8'-8"	El. 303'-8" 1'-0" ℄ Girder 8'-8"	1'-0" ℄ Girder 8'-8"	Part of TRUSS KT-3	14WF320 +PL 22x1 5/8 (B.S.) (Fy=42)	14WF455 (Fy=50)	
El. 284'	14WF342 (Fy=50)		14WF370 (Fy=50)	14WF320 (Fy=50)		14WF320 +PL 22x1½ (B.S.) (Fy=42) 36WF (12.JK1-24)	
El. 274'	14WF370 (Fy=50)	14WF95 (Fy=50)	14WF398 (Fy=50)	14WF342 (Fy=50)	14WF320 +PL 22x2 (B.S.) (Fy=42)	14WF320 +PL 2.2x1-3/4 (B.S.) (Fy=42)	
El. 264'		See Detail 10-JK2.35		14WF550 (Fy=50)			
El. 253	▲		▲	▲	▲	▲	
Top of base ℄	14WF500 (Fy=50) El. 248'-0"		14WF455 (Fy=50) El. 241'-0"	14WF320 +PL 22x2½ (B.S.) (Fy=42) El. 241'-0"	14WF320 +PL 22x2 5/8 (B.S.) (Fy=42) El. 241'-0"	14WF320 +PL 22x2 5/8 (B.S.) (Fy=42) El. 241'-0"	
Base Plate	62 x 7¼ x 5'-2"		66 x 8 x 5'-6"	75 x 9¼ x 6'-3"	78 x 9¾ x 6'-6"	76 x 9¼ x 6'-4"	

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

DRAWN S.C.
REVIEWED E.L.

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-K1-253