WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
6-11-68
9-4-68

	K59-1	K59-2	K59-3	K59-4	K59-5
El. 332'					
El. 310'				14WF87 (Fy=50)	
Street					
El. 294'	14WF119 (Fy=50)	14WF119 (Fy=50)	14WF103 (Fy=50)	℄ Girder K5A	14WF127 (Fy=50)
El. 284'				14WF158 (Fy=50)	
El. 274'			Truss KT-3		
El. 264'	14WF246 (Fy=50)	14WF246 (Fy=50)		14WF228 (Fy=50)	14WF184 (Fy=50)
El. 253	▲ 14WF246 (Fy=50)	▲ 14WF246 (Fy=50)		▲ 14WF237 (Fy=50)	▲ 14WF228 (Fy=50)
Top of base ℄	El. 248'-0"	El. 245'-0"		El. 241'-0"	El. 241'-0"
Base Plate	41 × 4 1/2 × 3'-8"	40 × 4 × 3'-7"		48 × 5 5/8 × 4'-3"	46 × 5 3/8 × 4'-1"

✱ Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

10-K1-258

9