WORTHINGTON, SKILLING, HELLE & JACKSON Civil & Structural Engineers

PROJECT THE WORLD TRADE CENTER | TITLE COLUMN SCHEDULE | DATE 5-15-67

REVISIONS

6-11-68

	K61-8	K61-9	K61-10				
El. 332'							
El. 310' Street							
El. 294'							
El. 284'	14WF103 (Fy=50)	14WF103 (Fy=50)	14WF111 (Fy=50)				
El. 274'							
El. 264'	14WF150 (Fy=50)	14WF150 (Fy=50)	14WF237 (Fy=50)				
El. 253	℄ Girder	℄ Girder	14WF237 (Fy=50) ▲				
Top of base ℄			El. 243'-4"				
Base Plate			39 - 4 = 3'-0"				

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-K1-265

LICENSED PROFESSIONAL ENGINEER
LESLIE E. ROBERTSON
No. 34360
UNIVERSITY OF THE STATE OF NEW YORK