WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE Zone K-2 | DATE: 5-15-67

REVISIONS
6-7-68
6-28-68

	K72-13	K72-14	K72-15	K72-16	K72-17	K72-18
El. 332'						
El. 310'						
El. 290'				14WF211 (Fy=50)	14WF193 (Fy=50)	14WF127 (Fy=50)
El. 279'-3"	14WF78 (Fy=42)	14WF78 (Fy=42)	14WF211 (Fy=50)			
El. 264'	Temp. bracing	Temp. bracing		14WF455 (Fy=50)	14WF426 (Fy=50)	14WF314 (Fy=50)
El. 253	20x1/2 I 2-PL's 12x5 1-PL 10x3 (Fy=50)	20x1/2 I 2-PL's 12x5 1-PL 10x3 (Fy=50)	14WF211 (Fy=50) ▲	14WF455 (Fy=50) ▲	14WF425 (Fy=50) ▲	14WF314 (Fy=50) ▲
Top of Base Pl.	El. 243'-4"	El. 243'-4"	El. 243'-4"	El. 243'-4"	El. 243'-4"	El. 243'-4"
Base Plate	39x4½x3'-5"	39x4½x3'-5"	39x3¾x3'-5"	53x5x4'-9"	49x5⅝x4'-5"	42x4⅝x3'-8"

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above sleb. See note on 10-JK2-2.
● See detail on 10-JK2-30.

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 3426 — UNIVERSITY OF ILL.

10-K1-271