WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE | DATE: 5-15-67

REVISIONS
6-7-68
6-28-68

	K75-16	K75-17	K75-18	K75-19	K75-20	K75-21	K75-22
El. 332'							
El. 310'							
El. 290'	14 WF 176 (Fy=50)	14 WF 119 (Fy=50)			14 WF 167 (Fy=50)	14 WF 184 (Fy=50)	14 WF 105 (Fy=50)
El. 279'-3"	detail 10 / 10-JK2-41	detail 11 / 10-JK2-41	14 WF 211 (Fy=50)	14 WF 211 (Fy=50)	Temp. Bracing	Temp. Bracing	
El. 264'	Temp. Bracing	Temp. Bracing	14 WF 211 (Fy=50)	14 WF 211 (Fy=50)	14 WF 211 (Fy=50)	14 WF 228 (Fy=50)	14 WF 264 (Fy=50)
El. 253	20 x 12 x 5 2 PL's 12 x 5 1 PL 10 x 3 (Fy=50)	20 x 12 x 5 2 PL's 12 x 5 1 PL 10 x 3 (Fy=50)	14 WF 211 (Fy=50)	14 WF 211 (Fy=50)	14 WF 287 (Fy=50)	14 WF 287 (Fy=50)	14 WF 264 (Fy=50)
Top of Base Pl.	El. 243'-4"	El. 243'-4"	El. 243'-4"	El. 243'-4"	El. 243'-4"	El. 243'-4"	El. 243'-4"
Base Plate	49 x 5¼ x 4'-7"	44 x 6 x 5'-10"	39 x 3¾ x 3'-5"	39 x 3¾ x 3'-5"	49 x 5⅝ x 4'-3"	49 x 5⅝ x 4'-3"	39 x 3¾ x 3'-5"

* Provide proper splice pls., bolt holes & finished col. top for future columns. Use upper col. one size smaller except as shown.
▲ See detail on 10-JK4-3 and 4.
■ Splice 3" above slab. See note on 10-JK2-2.
● See detail on 10-JK2-30.

10-K1-270

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

C