WORTHINGTON, SKILLING, HELLE & JACKSON — Civil & Structural Engineers

PROJECT: THE WORLD TRADE CENTER | TITLE: COLUMN SCHEDULE - NEW COLUMNS HOTEL AREA | DATE: 12-23-71

REVISIONS

11-27-72

	H-P1	H-P2	H-P3	H-P4	H-P5	H-P6	H-P7
3'-0" / El. 332'	See Dwg. Book 13	3'-0" See D.B. 13	See D.B. 13	See D.B. 13	See D.B. 13	See D.B. 13	
El. 310'							
3'-0" / El. 294'	*	*	*	*	*	*	2" 10-JK5-2 A
El. 284'	14WF426 Fy36	14WF426 Fy36	14WF193 Fy36	14WF193 Fy36	14WF455 Fy36	14WF455 Fy36	See 10-JK5-2 / 14WF264 Fy36 10-JK5-2 A
3'-0" / El. 274'	③	③	③	③	③	③	③ 10-JK5-2 A
El. 264'							Shear studs 10-JK5-2 A
El. 253	14WF500 Fy36	14WF500 Fy36	14WF219 Fy36	14WF219 Fy36	14WF500 Fy36	14WF500 Fy36	14WF264 Fy36
Top of base Pl at El. 241'							
Base Plate	60"x6¾"x5'-6" ① Fy36	60"x6¾"x5'-6" ① Fy36	41"x4'8"x3'-8" ① Fy36	41"x4'8"x3'-8" ① Fy36	60"x9½"x5'-6" ①② Fy36	60"x6¾"x5'-6" ① Fy36	45"x4'8"x4'-0" ① Fy36

* Provide proper splice pls., bolt holes & finished col. top for future columns. See 10-JK2-4.

① See 10-JK3-2
② See Det. S 8-JK5-9.5
③ See 10-JK2-4

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

DESIGNED K. CHIANG
DRAWN A. FRANQUI
REVISED W. Pincus

10-K1-299

A