SKILLING, HELLE, CHRISTIANSEN, ROBERTSON — Structural & Civil Engineers

PROJECT THE WORLD TRADE CENTER | TITLE SCHEDULE FOR SHEAR CONNECTORS | DATE 7-19-68

REVISIONS

Schedule "A"

Beam No.	Stud Size	No. Of Rows		Zone 1	Zone 2	Zone 3
100	7/8"ϕ×3½"	3	Length			
			Spacing	4½"	4½"	4½"
101	7/8"ϕ×3½"	2	Length	4'-0"		
			Spacing	4"	7½"	7½"
102	7/8"ϕ×3½"	2	Length	7'-6"		
			Spacing	4"	7½"	7½"
103	7/8"ϕ×3½"	2	Length	6'-0"		
			Spacing	3"		
104	7/8"ϕ×3½"	2	Length	7'-6"		
			Spacing	3"	4½"	4½"
105	7/8"ϕ×3½"	2	Length	6'-0"	4'-0"	
			Spacing	4"	6"	7½"
106	7/8"ϕ×3½"	2	Length	5'-0"	5'-0"	
			Spacing	3"	4"	5½"
107	7/8"ϕ×3½"	2	Length	6'-0"	6'-0"	
			Spacing	5"	7½"	10½"
108	7/8"ϕ×3½"	3	Length	10'-0"		
			Spacing	3"	7"	7"
109	7/8"ϕ×3½"	3	Length	5'-0"		
			Spacing	4"	9"	9"
110	7/8"ϕ×3½"	3	Length	5'-0"		
			Spacing	5"	6"	6"
111	7/8"ϕ×3½"	3	Length	10'-0"		
			Spacing	5"	6"	6"
112	7/8"ϕ×3½"	3	Length	5'-0"		
			Spacing	3"	15"	15"
113	7/8"ϕ×3½"	3	Length	5'-0"		
			Spacing	3½"	10½"	10½"
114	7/8"ϕ×3½"	3	Length	6'-0"	5'-0"	
			Spacing	3"	3½"	7"
115	7/8"ϕ×3½"	3	Length	6'-0"	4'-0"	
			Spacing	3"	4½"	8"
			Length	5'-0"	5'-0"	

Schedule "A"

Beam No.	Stud Size	No. Of Rows		Zone 1	Zone 2	Zone 3
118	7/8"ϕ×3½"	4	Length	5'-0"	5'-0"	
			Spacing	3"	9"	12"
119	7/8"ϕ×3½"	2	Length	5'-0"		
			Spacing	3"	5¾"	5¾"
			Length			
			Spacing			
			Length			
			Spacing			
			Length			
			Spacing			
			Length			
			Spacing			
			Length			
			Spacing			
			Length			
			Spacing			
			Length			
			Spacing			
			Length			
			Spacing			
			Length			
			Spacing			
			Length			
			Spacing			

Note:

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

DESIGNED