SKILLING, HELLE, CHRISTIANSEN, ROBERTSON — Structural & Civil Engineers

PROJECT THE WORLD TRADE CENTER | TITLE SCHEDULE FOR SHEAR CONNECTORS | DATE 11-5-68

REVISIONS

Schedule "A"

Beam No.	Stud Size	No. Of Rows		Zone 1	Zone 2	Zone 3
252	7/8"ϕx3½"	4	Length	4'-0"	6'-0"	
			Spacing	5"	7"	16½"
253		4	Length	4'-0"	6'-0"	
			Spacing	3¼"	4½"	12½"
254		4	Length	4'-0"	6'-0"	
			Spacing	5½"	7¾"	18"
255		4	Length	4'-0"	6'-0"	
			Spacing	3¾"	5¼"	15"
256		4	Length	4'-0"	6'-0"	
			Spacing	4½"	6"	15¼"
257		6	Length	4'-0"	6'-0"	
			Spacing	4¼"	5"	7¾"
258		4	Length	4'-0"	6'-0"	
			Spacing	3¼"	4"	5¾"
259		4	Length	4'-0"	6'-0"	
			Spacing	3½"	4¼"	7¼"
260		4	Length	4'-0"	6'-0"	
			Spacing	4½"	6"	12"
261		4	Length	4'-0"	6'-0"	
			Spacing	5¼"	7"	13½"
262		4	Length	4'-0"	6'-0"	
			Spacing	5"	6¾"	16½"
263		4	Length	4'-0"	6'-0"	
			Spacing	5¼"	7¾"	18½"
264		4	Length	4'-0"	6'-0"	
			Spacing	4¾"	6½"	15"
265		4	Length	4'-0"	6'-0"	
			Spacing	4¾"	6½"	16"
266		2	Length	4'-0"	6'-0"	
			Spacing	4"	5½"	14½"
267		2	Length	4'-0"	6'-0"	
			Spacing	4½"	6½"	16½"
			Length	4'-0"	6'-0"	

Schedule "A"

Beam No.	Stud Size	No. Of Rows		Zone 1	Zone 2	Zone 3
270	7/8"ϕx3½"	2	Length	4'-0"	6'-0"	
			Spacing	6"	8"	18"
271		2	Length	4'-0"	6'-0"	
			Spacing	5¼"	7"	15¾"
272		2	Length	4'-0"	6'-0"	
			Spacing	5¼"	7¼"	16"
273		2	Length	4'-0"	6'-0"	
			Spacing	5¾"	8¼"	17"
274		4	Length	4'-0"	6'-0"	
			Spacing	3"	4"	9"
275		2	Length	4'-0"	6'-0"	
			Spacing	3¼"	4½"	10"
276		2	Length	4'-0"	6'-0"	
			Spacing	4½"	6¼"	13½"
277		2	Length	4'-0"	6'-0"	
			Spacing	3¼"	5¾"	
278		4	Length	4'-0"	6'-0"	
			Spacing	5"	8¾"	
279		2	Length	4'-0"	6'-0"	
			Spacing	4¼"	10"	
280		4	Length	4'-0"	6'-0"	
			Spacing	4½"	6¾"	23"
281		2	Length	4'-0"	6'-0"	
			Spacing	3½"	3½"	
282		4	Length	4'-0"	6'-0"	
			Spacing	5¼"	5¼"	
283		2	Length	4'-0"	6'-0"	
			Spacing	3½"		
284	7/8"ϕx3½"	2	Length	4'-0"	6'-0"	
			Spacing	3½"	5½"	5½"

Notes:

1. See Dwg. 12-1132.9 for explanation

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

DESIGNED