SKILLING, HELLE, CHRISTIANSEN, ROBERTSON — Structural & Civil Engineers

PROJECT THE WORLDTRADE CENTER | TITLE SCHEDULE FOR SHEAR CONNECTORS | DATE 11-5-68

REVISIONS

Schedule "A"

Beam No.	Stud Size	No. Of Rows		Zone 1	Zone 2	Zone 3
285	7/8"ϕx3½"	2	Length	4'-0"	6'-0"	
			Spacing	4½"	7¾"	
286		2	Length	5'-0"		
			Spacing	7½"		
287		2	Length	4'-0"	6'-0"	
			Spacing	7¼"	9¾"	21½"
288		2	Length	4'-0"	3'-0"	
			Spacing	5¾"	12½"	
289		2	Length	4'-0"	3'-0"	
			Spacing	5"	11¾"	
290		2	Length	4'-0"	6'-0"	
			Spacing	4½"	7½"	
291		2	Length	4'-0"	3'-0"	
			Spacing	6"	13½"	
292		2	Length	4'-0"	3'-5"	
			Spacing	4"	8¾"	
293		2	Length	4'-0"	6'-0"	
			Spacing	4"	6½"	
294		2	Length	4'-0"	6'-0"	
			Spacing	5¾"	9½"	
295		2	Length	4'-0"	6'-0"	
			Spacing	4½"	6"	13½"
296		2	Length	4'-0"	6'-0"	
			Spacing	3"	4"	9"
297		2	Length	4'-0"	6'-0"	
			Spacing	5¾"	8"	17½"
298		4	Length	4'-0"	6'-0"	
			Spacing	3½"	5"	11"
299		2	Length	4'-6"		
			Spacing	4¾"		
701		4	Length	4'-0"	6'-0"	
			Spacing	4¾"	7¼"	24"
703			Length	4'-0"	6'-0"	

Schedule "A"

Beam No.	Stud Size	No. Of Rows		Zone 1	Zone 2	Zone 3
704	7/8"ϕx3½"	2	Length	4'-0"	5'-0"	
			Spacing	4½"	7¼"	
705		4	Length	4'-0"		
			Spacing	5¼"	12"	
706		4	Length	4'-0"		
			Spacing	4¼"	10"	
707		2	Length	4'-0"	3'-0"	
			Spacing	5½"	12½"	
708		2	Length	4'-0"		
			Spacing	6¾"	12½"	
709		3	Length	4'-0"	6'-0"	
			Spacing	3½"	5¾"	
710		2	Length	4'-0"	6'-0"	
			Spacing	4"	6¾"	
711		2	Length	4'-6"		
			Spacing	4"		
712		2	Length	4'-0"		
			Spacing	5¼"		
713		4	Length	4'-0"		
			Spacing	4¾"		
714		2	Length	4'-0"	6'-0"	
			Spacing	5"	8¼"	24"
715		2	Length	4'-0"		
			Spacing	9¾"	9¾"	
716		2	Length	4'-0"	6'-0"	
			Spacing	3¾"	6½"	
717		2	Length	4'-0"		
			Spacing	6¾"		
718		2	Length	4'-0"	6'-0"	
			Spacing	5¾"	8"	19"
719		2	Length	4'-0"		
			Spacing	7¾"	22"	
720			Length	4'-0"	6'-0"	

LESLIE E. ROBERTSON — LICENSED PROFESSIONAL ENGINEER — No. 34360 — STATE OF NEW YORK

RELEASED