SKILLING, HELLE, CHRISTIANSEN, ROBERTSON — Structural & Civil Engineers

PROJECT THE WORLD TRADE CENTER | TITLE SCHEDULE FOR SHEAR CONNECTOR | DATE 9-20-68

REVISIONS

SCHEDULE "B"

For beams not included in tables 12-JK2-20 thru. 31

Beam No.	Stud Size	No. Of Rows	Total No. Of Studs	Beam No.	Stud Size	No. Of Rows	Total No. Of Studs
301	¾"ø x 3"	3	171				
302	¾"ø x 3"	3	174				
303	¾"ø x 3"	2	54				

Note:
1. See notes on 12-JK2-20 for further description of studs.
2. All studs to be spaced uniformly over the length of beam

LICENSED PROFESSIONAL ENGINEER — LESLIE E. ROBERTSON — No. 34360 — UNIVERSITY OF THE STATE OF NEW YORK

DESIGNED

DRAWN

REVIEWED

12-JK2-18