PROJECT: HARRY STREET BRIDGE OVER TRADE CENTER - MODIFICATION

INDEX & GENERAL NOTES

DATE: 6-28-73

Index

19-X4-1 Index & General Notes
19-X4-2.1 Details at North Support.
2.2 Details at North Support.
2.3 Details at North Support.
2.4 Details at North Support.

19-X4-3.1 Details at Center Support.
3.2 Details at Center Support.
3.3 Details at Center Support.

General Notes - Concrete

1. All construction shall be in accordance with Basic Project Specifications.
2. See SCK-102 for framing Plan at North and Center Supports.
3. Remove existing concrete without damage to existing reinforcing.
4. Clean face of existing concrete and thoroughly coat entire surface with approved epoxy bonding compound prior to casting new concrete.
5. New concrete shall be approved "non-shrink," f'_c = 4000 psi stone aggregate concrete.

LICENSED PROFESSIONAL ENGINEER
LESLIE E. ROBERTSON
No. 34360
OF THE STATE OF NEW YORK

DESIGNED WAB
DRAWN
REVIEWED

19-X4-1